

**Proposed Earth work excavation allround the existing Building at Kasvanahalli KRJS premises.**

| <b>SI No</b> | <b>Description</b>   | <b>Unit</b> | <b>App.Qty</b> | <b>Rate</b>     | <b>Amount</b> |
|--------------|--|-------------|----------------|-----------------|---------------|
| <b>1.0</b>   | Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work. <b>In all kinds of soils upto 300 mm depth</b> | <b>Cmtr</b> | <b>1260.00</b> |                 |               |
| <b>2.0</b>   | Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage <b>In all kinds of soils Depth upto 3 m</b>   | <b>Cmtr</b> | <b>5797.0</b>  |                 |               |
| <b>3.0</b>   | Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage <b>Depth 3 m to 6 m</b>   | <b>Cmtr</b> | <b>146.00</b>  |                 |               |
| <b>4.0</b>   | Transportation for excavated earth up to 400 mtr distance by Tipper capacity 17 m3 ( inside the premises.)   | <b>Load</b> | <b>425.00</b>  |                 |               |
|              |  |             |                |                 |               |
|              |  |             |                |                 |               |
|              |  |             |                | <b>Gr.Total</b> |               |